

3 January 2019

Request for Proposal for Stage – Service RFP – 038/2018

Eurovision Song Contest 2019

Answers to Requests for Clarification – part 1

1. The answers to requests for clarifications attached hereto as **Appendix A** are provided by ESC 2019 pursuant to section D.1 of the above Request for Proposals ("**the RFP**").
2. ESC 2019's responses below shall be deemed for all intents and purposes as part of the RFP and will bind all Respondents thereto but will not alter or derogate from the provisions of the RFP unless expressly stated otherwise.
3. These responses will be provided to all Respondents. Respondents must attach a copy of these responses, duly signed by an authorized signatory to indicate acceptance, to their Proposal.

KAN - the Israeli Broadcasting Corporation

We hereby confirm the contents of these **Answers to Requests for Clarification**, including our acknowledgement of any consequent changes to the RFP.

Respondent's signature

Appendix A – Answers to Clarification inquiries

No	Article	Question	Answer
1	F.5.2 - PRISM LEGS	AutoCAD files or side view of the legs is required.	The preliminary Floorplan Main Set and Green Room will be supplied separately to Respondents, following the signature of a non-disclosure agreement
2	F.5.2 - PRISM LEGS	What is the construction volume (height/width)?	<ul style="list-style-type: none"> - length (large legs): approx. 25mtr. - length (small legs): approx. 18mtr. - max. width (large): approx. 3,75mtr. - max. width (small): approx. 2,10mtr. - max. height: approx. +18,00mtr.
3	F.5.2 - <i>"Possibly with the option to attach additional lighting fixtures in the inside"</i>	what weight estimate should we calculate by?	<ul style="list-style-type: none"> - no information about lighting fixtures until now - t.b.d.
4	F.5.3 - PRISM CATWALKS – <i>"As rehearsals will evoke bad scratches on the Perspex, the top surface needs 2 extra layers to cover overnight before and during the show week"</i>	<p>Does the 2 extra layers need to be transparent?</p> <p>By who will the covering overnight work is done?</p>	<ul style="list-style-type: none"> - yes! - the extra layers have to be exactly the same and they always have to be changed for the scratched ones <p>The stage builder.</p>
5	F.4.5. – BRIDGES	<p>AutoCAD files or side view of the bridge is required.</p> <p>What is the required surface cover?</p>	<p>The preliminary Floorplan Main Set and Green Room will be supplied separately to Respondents, following the signature of a non-disclosure agreement</p> <ul style="list-style-type: none"> - same surface as the prism catwalks <i>"steel construction, outside clad by segments of mirror-laminated Perspex with flex-led in joints between the single segments"</i>
6	F.4.5. – BRIDGES	what is the clear span of the bridge?	- the length incl. all steps are approx. 10mtrs. = span of 10mtrs.

7	F.5.5. - CENTER CATWALK	Does the stairs at the end moves with the catwalk?	- ideally yes, but could possibly be removable separately
8	F.5.6. – STAGE RAMPS – <i>"Lengths: 2x 14mtrs. + 5mtrs. rostra on stage level"</i>	Width of the ramp on the floorplan doesn't scale to the mentioned dimension What is the right width of the ramp?	- width=4 mtrs. (description is according to the drawing) - plus a rostrum, L=5mtrs. at the end of each ramp - 2x 14 means = two ramps of 14mtrs.
9	SCRIM	Should we supply the rail itself or only the fabric? If so, does the - <i>"Automation (supplied by third party supplier)"</i> Refers to the moving of the screen? If so, does the operating during shows also by third party?	- only the fabric including the hangers (rail and automation system and operating person should come together from a third-party supplier)
10	Green Room - F.6.2 - PRISM LEGS	AutoCAD files or side view of the element is required. What is the construction volume (height/width)?	The preliminary Floorplan Main Set and Green Room will be supplied separately to Respondents, following the signature of a non-disclosure agreement - length (of each): approx. 50mtr. - max. width: approx. 2,00mtr. - max. height: approx. 8,00mtr.
11	F.6.5 – SOFAS	on your request mentioned 16 sofas while on the floorplan we count 26. What will be the right quantity?	- 26 sofas - means 104 identical segments
12	F.6.1.- HOLDING AREA platform	Is there a specification on railing around the platforms?	- just functional and covered with black molton